

Case Study

Project

The construction of a new paper reel manufacturing and distribution plant in Partington near Manchester (UK) with a total value estimated at circa £100M.

Site of a former fuel oil storage depot and oil tanker terminal adjacent to and accessed from the Manchester ship canal.

Client

SAICA Containerboard UK Ltd

Budget

£150K

Overview

General demolition, site clearance and remediation works, including: breaking out of old foundations, construction of surcharge mounds, cement/lime stabilization of soft ground followed by piling for heavy foundations and ancillary structures.

The main building structure and external works were designed by IDOM (Zaragoza) including: foundations, main structural frame, secondary steelworks, offices and mezzanine areas, plant and machinery foundations, retaining walls water treatment facilities, drainage, pavements and parking areas.

Other specialist activities carried out to prepare the site include: security controls, communications systems, fire controls and sprinklers, electrical control systems, automatic transportation and conveyor distribution systems.

Services provided

Merebrook acted as CDMC for the initial groundworks improvements and also provided on site Project Management resources for elements of the civil engineering construction works and liaison with the main service providers.

